

How to arrange for your water mains, water service connections and other components to be adopted by South West Water/Bournemouth Water

Stage 5: Connect Mains (SLP to make the Final Connection)

Where Final Connection of the Self-Laid Main to the Network is to be carried out by the Self-Lay Provider

Information provided by you (applicant)	Additional comments
<p>Provide details of Self-Lay Works to be connected to the Network:</p> <ul style="list-style-type: none"> • Submit CRMC paperwork according to WIRS. • Date of proposed connection. • Construction records indicating Self-Laid Mains to be connected electronically in CAD and PDF format or as otherwise agreed with the Water Company. • Contact details of responsible competent person. • Prepare method statements and risk assessment documents compliant as a minimum with the Water Company published Design and Construction Specification. • Update Weekly Whereabouts with Final Connection date (by email or as otherwise agreed by the Water Company). <p><i>Following submission of Testing results in SLPM 4/2 or concurrently if date of Final Connection is known.</i></p> <p><i>Comply with the Water Company published Design and Construction Specification, the Annual contestability Summary and the Agreement (CDM and HSE requirements and specific Water Company authorisation and approvals procedures i.e. “safe control of operations”).</i></p> <p><i>CRMC paperwork provided by WIRS as part of accreditation.</i></p> <p><i>Flushing may be necessary if likely demand on the new Self-laid Main is insufficient to maintain a suitable level of turnover. SWW/BW and customer discuss the anticipated programme and activities and a flushing programme shall be agreed prior to consenting the Self-lay Works connection if deemed necessary by SWW/BW.</i></p>	
<p>Information provided by us (South West Water)</p>	
<p>We will review documents provided by the SLP in Stage 4 and agree proposed Final Connection date by written response in accordance with the published DCS and ACS.</p> <p>A part of the review of the supporting documents to determine SLP evidence of competency for activities relative to WIRS, the SLP and Water Company coordinates any requirements regarding connection method, standby resources, or materials etc. as agreed at design acceptance (Stage 2).</p>	

Information provided by you (applicant)	
<p>Following an agreed Final Connection, completion notification shall be issued by the SLP to the Water Company within 24 hours.</p> <ul style="list-style-type: none">• Completed Certificate of Vesting• Construction records indicating Self-Laid Mains that have been connected electronically in CAD and PDF format or as otherwise agreed with SWW/BW. <p>Industry standard Certificate of Vesting should be used, as defined in the MWAA.</p>	

Proceed to Stage 6: Vest new mains and correct any defects